

St. Charles Parish
Road Maintenance 2011
Parish Project P090103-9
Alternate 2

Street, Road, or Lane Name	District	2" Cold Plane and Overlay	
		Cold Plane (SQ YARD)	Overlay (Ton)
Spillway Road	6	4,923.9	542
TOTAL		4,924	542

Street, Road, or Lane Name	District	6" Asphaltic Concrete Patching	
		Patch Area (SQ YARD)	Patching (Ton)
Burguieres Lane	1	5	2
Spillway Road	6	299	98
TOTAL		304	100

Street, Road, or Lane Name	District	3" Asphalt pavement
		Asphalt Pavement (Ton)
Elm Street	1	98
Burguieres Lane	1	13
Perry Lane	2	54
TOTAL		165

Street, Road, or Lane Name	District	Common Excavation "Net Section" (CY)
Elm Street	1	383
Burguieres Lane	1	20
Perry Lane	2	83
TOTAL		486

Street, Road, or Lane Name	District	Fill	
		Structural Fill (CY)	Limestone Base (CY)
Elm Street	1	200	133
Perry Lane	2	111	74
TOTAL		311	207

Street, Road, or Lane Name	District	Grade and Shape Existing Base (SQ YARD)
Burguieres Lane	1	83
TOTAL		83

Street, Road, or Lane Name	District	Concrete Walk
Median of Longview Dr. at River Rd.	1	1
TOTAL		1

Street, Road, or Lane Name	District	Handicap Curb Ramp
Eastern corners of Longview Dr. and San Francisco Dr.	1	2
Western corners of Longview Dr. and Eve St.	1	2
TOTAL		4

1. AREAS REQUIRING PATCHING WILL BE MARKED WITH ORANGE SPRAY PAINT PRIOR TO THE START OF CONSTRUCTION

* QUANTITIES LISTED ABOVE DO NOT REPRESENT ALL CONTRACT QUANTITIES, FOR COMPLETE QUANTITIES LIST SEE SECTION 00300.