

**SECTION 00806**

**CHANGE ORDER**

No. One (1) - FINAL

DATE OF ISSUANCE June 14, 2017

EFFECTIVE DATE 8/31/17

OWNER St. Charles Parish Government

CONTRACTOR Baker Pile Driving and Sitework, LLC

Contract: P081102-7

Project: Dunleith Canal Bank Stabilization, Phase 6

OWNER's Contract No. P081102-7 ENGINEER's Contract No. 2008-800

ENGINEER Evans-Graves Engineers, Inc.

You are directed to make the following changes in the Contract Documents:

**Description:** *See attached example on how to fill in this information*

1. Delete the Following Work Items:

a. (none)

Total of Deducted Items = (0.00)

2. Add the Following Work Items:

a. New Contract Item: X-1) Liquidated Damages - Alpha Testing Extended Services.

Deduction of \$5,651.50 L.S. See attached budget extension request.

Total of Added Items = (-\$5,651.50)

3. Revise the Following Work Item Quantities:

a. Contract Item #3: Embankment

The quantity is to be changed to 1,372 Cubic Yard (+\$17,418.24)

b. Contract Item #8: 4" or Smaller PVC Pipe Penetration Through Sheet Pile Wall

The quantity is to be changed to 6 Each (+\$647.64)

c. Contract Item #9: 6" PVC Pipe Penetration Through Sheet Pile Wall

The quantity is to be changed to 1 Each (-\$2,740.50)

d. Contract Item #11: Sheet Pile Modification for Underground Obstructions

The quantity is to be changed to 65 Linear Feet (-\$1,800.00)

e. Contract Item #15: Relocation of Infrastructure Items

The quantity is to be changed to 0 (-\$30,000.00)

Total of Change in Work Items Quantity = (-\$16,474.62)

**Reason for Change Order:** Final quantity balances and imposition of liquidated damages.

1. Deleted Work Items

a. N/A.

2. Add Work Items

a. The testing laboratory services of Alpha Testing and Inspection, Inc. for vibration monitoring services during pile driving operations extended beyond the limits of the initial proposal due to the slow production and pile driving operations of the Contractor.

3. Revise Work Item Quantities

a. A greater quantity of embankment was needed to complete the contract work than was anticipated in the bid documents; largely due to the presence of rock and debris hidden in the embankment

behind and beneath the vegetative overgrowth, which had to be removed in order to provide a firm embankment behind the new sheet pile wall.

- b. One additional 4" or smaller pipe penetration was encountered during the contract work, which was not visible during the project site survey or walkthrough because it was hidden in the embankment behind and beneath the vegetative overgrowth.
- c. Fewer 6" pipe penetrations were encountered during the contract work than were anticipated in the bid documents.
- d. There were fewer obstructions encountered during the contract work than anticipated in the bid documents.
- e. No infrastructure items to be relocated were encountered during the contract work.

**Attachments:** (1) Tabulation of Project Quantities, dated June 14, 2017

CHANGE IN CONTRACT PRICE:	
Original Contract Price	
\$ <u>869,321.54</u>	
Net Increase (Decrease) from previous Change Orders No. ___ to ___:	
\$ <u>0.00</u>	
Contract Price prior to this Change Order:	
\$ <u>869,321.54</u>	
Net <u>increase (decrease)</u> of this Change Order:	
\$ <u>(-22,126.12)</u>	
Contract Price with all approved Change Orders:	
\$ <u>847,195.42</u>	

CHANGE IN CONTRACT TIMES:	
Original Contract Times:	150 calendar days
Substantial Completion:	March 9, 2017
Ready for final payment:	April 23, 2017 (days or dates)
Net change from previous Change Orders No. ___ to No. ___:	
Substantial Completion:	N/A
Ready for final payment:	N/A (days)
Contract Times prior to this Change Order:	
Substantial Completion:	March 9, 2017
Ready for final payment:	April 23, 2017 (days or dates)
Net <u>increase (decrease)</u> this Change Order:	
Substantial Completion:	add 8 calendar days
Ready for final payment:	add 8 calendar days (days)
Contract Times with all approved Change Orders:	
Substantial Completion:	March 17, 2017
Ready for final payment:	May 1, 2017 (days or dates)

RECOMMENDED:  
 By: [Signature]  
 ENGINEER (Authorized Signature)  
 Date: 6/16/17

APPROVED:  
 By: [Signature]  
 OWNER (Authorized Signature)  
 Date: 8/3/17

ACCEPTED:  
 By: [Signature]  
 CONTRACTOR (Authorized Signature)  
 Date: 6/19/17




PROJECT TITLE: DUNLEITH CANAL STABILIZATION - PHASE 6

PROJECT NO: P081102-7

TABULATION OF PROJECT QUANTITIES

June 14, 2017



**EVANS-GRAVES  
ENGINEERS, INC.**

ITEM	DESCRIPTION	QTY	UNIT	Bid of Baker Pile Driving and Site Work, LLC		Change Order C01		Final Including C01	
				UNIT PRICE	AMOUNT	QTY	AMOUNT	QTY	AMOUNT
1	Mobilization	1	Lump Sum	\$71,000.00	\$71,000.00	0.00	\$0.00	1.00	\$71,000.00
2	Clearing and Grubbing	1	Lump Sum	\$11,692.00	\$11,692.00	0.00	\$0.00	1.00	\$11,692.00
3	Embankment	940	Cubic Yard	\$40.32	\$37,900.80	432.00	\$17,418.24	1,372.00	\$55,319.04
4	Sheet Piling (35' Long)	29,750	Square Feet	\$20.00	\$595,000.00	0.00	\$0.00	29,750.00	\$595,000.00
5	Sheet Pile Wall End Section (20' Long)	1	Each	\$11,942.00	\$11,942.00	0.00	\$0.00	1.00	\$11,942.00
6	Sheet Pile Wall Cap	850	Linear Feet	\$69.00	\$58,650.00	0.00	\$0.00	850.00	\$58,650.00
7	Work Platform	1	Lump Sum	\$7,650.00	\$7,650.00	0.00	\$0.00	1.00	\$7,650.00
8	4" or Smaller PVC Pipe Penetration Through Sheet Pile Wall	5	Each	\$647.64	\$3,238.20	1.00	\$647.64	6.00	\$3,885.84
9	6" PVC Pipe Penetration Through Sheet Pile Wall	4	Each	\$913.50	\$3,654.00	-3.00	-\$2,740.50	1.00	\$913.50
10	18" HDPE Pipe Penetration Through Sheet Pile Wall	3	Each	\$2,150.00	\$6,450.00	0.00	\$0.00	3.00	\$6,450.00
11	Sheet Pile Modifications for Underground Obstructions	85	Linear Feet	\$90.00	\$7,650.00	-20.00	-\$1,800.00	65.00	\$5,850.00
12	Solid Sod	378	Square Yard	\$19.43	\$7,344.54	0.00	\$0.00	378.00	\$7,344.54
13	Hydroseed	1,040	Square Yard	\$2.52	\$2,620.80	0.00	\$0.00	1,040.00	\$2,620.80
14	Construction Layout	1	Lump Sum	\$6,300.00	\$6,300.00	0.00	\$0.00	1.00	\$6,300.00
15	Relocation of Infrastructure Items	1	Lump Sum	\$30,000.00	\$30,000.00	-1.00	-\$30,000.00	0.00	\$0.00
16	Demolition and Removal of Existing Timber Bulkhead	1	Lump Sum	\$2,860.20	\$2,860.20	0.00	\$0.00	1.00	\$2,860.20
17	Concrete Paved Swale, 16"W x 4"D	1	Lump Sum	\$3,704.00	\$3,704.00	0.00	\$0.00	1.00	\$3,704.00
18	Removal of Wood Fence (No Disposal)	60	Linear Feet	\$27.75	\$1,665.00	0.00	\$0.00	60.00	\$1,665.00
X-1	Liquidated Damages - Alpha Testing Extended Services	0	Lump Sum	\$0.00	\$0.00	1.00	-\$5,651.50	1.00	-\$5,651.50

TOTALS

\$869,321.54

-\$22,126.12

\$847,195.42