CHANGE ORDER

No. <u>2</u>

DATE OF ISSUANCE11/15/16	EFFEC	EFFECTIVE DATE		
OWNER: St. Charles Parish CONTRACTOR Sealevel Construction				
Contract: Willowridge Drainage Pump Stroject: Willowridge Drainage Pump Sta				
OWNER's Contract No. P080905-4A ENGINEER Burk Kleinpeter, Inc.	State Project No. H.010102	ENGINEER's Contract No. 12.019		

You are directed to make the following changes in the Contract Documents:

Summary:

1. Contractor to drive sheet piles provided by the Owner in the discharge basin to prevent erosion on the property line and ensure flow path to existing natural drainage canal. Contractor to drive sheets using equipment currently on site, no additional cost for mobilization or demobilization.

Description:

- 1. Delete the Following Work Items:
 - a. N/A
- 2. Add the Following Work Items:
 - a. New Contract Item 60: Work Change Directive #6

 Drive owner provided sheet piles
 QTY: 2,550 SF, 12.90\$/SF,
 Addition of \$ 32,895.00.

Total of Added Work Items = +\$32,895.00

- 3. Revise the Following Work Item Quantities:
 - a. N/A

Reason for Change Order: List a reason for each Line Item listed above. See attached example on how to fill in this information

- 1. Deleted Work Items
 - a. N/A
- 2. Add Work Items
 - a. Upon commencement of discharge basin work, it was recognized that there was the potential for discharge of pumped water to flow onto the neighboring property. As a precaution to prevent the water from flowing onto the neighboring property, sheet piles were driven along the back of the property line and the west side of the discharge basin to deflect the discharged water from the neighboring property and direct the discharged water into the natural drainage canal per the permit conditions. (WCD #6)
- 3. Revise Work Item Quantities
 - a. N/A
- 4. Change in Contract time Additional 14 days due to the following.
 - a. 14 days to drive sheet piles (WCD #6)

Attachments: Work Change Directive 6

CHANGE IN CONTRACT PRICE:	CHANGE IN CONTRACT TIMES:
Original Contract Price \$ 5,572,160.00	Original Contract Times: Substantial Completion: 12/30/16 Ready for final payment: 12/30/16 (days or dates)
Net Increase (Decrease) from previous Change Orders No1_ to _1: \$_60,059.00	Net change from previous Change Orders No1 to No1: Substantial Completion: Plus 43 Days Ready for final payment: Plus 43 Days (days)
Contract Price prior to this Change Order: \$5,632,219.00	Contract Times prior to this Change Order: Substantial Completion: 2/11/2017 Ready for final payment: 2/11/2017 (days or dates)
Net increase (decrease) of this Change Order: \$_32,895.00	Net increase (decrease) this Change Order: Substantial Completion: 14 Days Ready for final payment: 14 Days (days)
Contract Price with all approved Change Orders: \$_5,665,114.00	Contract Times with all approved Change Orders: Substantial Completion: 2/25/17 Ready for final payment: 2/25/17 (days or dates)
RECOMMENDED: By:	ACCEPTED: By: Accepted: Contractor (Authorized Signature) Date: 28 000 100

SECTION 00805

WORK CHANGE DIRECTIVE

<u>No.</u>
DATE OF ISSUANCE September 2, 2016 EFFECTIVE DATE
Owner: St. Charles Parish
Contractor: Sealevel Construction Inc.
Contract:
Project: Willowridge Drainage Pump Station
Owner's Contract No.: P080905-4A Engineer's Contract No.: NO.12.019
ENGINEER: Burk-Kleinpeter, Inc.
Contractor is directed to proceed promptly with the following change(s):
Description: Contractor to drive sheet piles provided by the Owner in the discharge basin to prevent erosion Contractor to use crane currently on site.
New Contract Item 60: Drive owner provided sheet piles QTY: 2,550 SF, 12.90\$/SF, \$32,895.00 total.
Attachments: Proposal from Sealevel Construction Inc., Dated 8/31/16. Sheet M2.0, Pumping Station Plan Rev 2 "Work Change Directive – 8/24/16"
Purpose for Work Change Directive: Directive to proceed promptly with the Work described herein, prior to agreeing to changes on Contract Price and Contract Time, is issued due to: (check one)
☐ Non-agreement on pricing of proposed change.
x Necessity to proceed for schedule or other project reasons.
Estimated Change in Contract Price and Contract Times (non-binding, preliminary):
Contract Price: \$ 32,895 increase
Contract Time: 14 days increase
Basis of estimated change in Contract Price:
□ Lump Sum x Unit Price
☐ Cost of the Work ☐ Other
Recommended: Limited Authorization By*: Received: By: By: By: By: By: Sonfactor (Authorized Signature)
Title: EKEC. VICE PRES. Title: Second Togoth sunfide: PESIDENT Date: 9/1/20/L Date: 9-8-16 Date: 7/567 NO *Owner's Representative is not authorized to finalize a Change Order nor does the Work Change Directive substitute the Change
Order process as more fully set out in the General Conditions of the Construction Contract.
Approved by Funding Agency (if applicable)
By: Date:
Title:

Proposal

From:

SEALEVEL CONSTRUCTION INC.

P.O. Box 1037

Thibodaux, LA 70302 Phone: 985.448.0970 Fax: 985.448.0922 Project: Description: 15176 WCD#

WILLOWRIDGE PUMP STATION ADDITIONAL SHEET PILE & RIP

ITEM	DESCRIPTION	BID QTY U/M	UNIT BID	AMOUNT
10	STEEL SHEET PILE WINGWALL	2,550.000 SF	12.90	\$32,895.00
			TOTAL BID:	\$32.895.00

Signature:

Richard J Roth, President

Qualifications:

- 1) The sheet pile materials shall be supplied by St Charles Parish and shall be in a condition to allow for installation
- 2) This proposal does not include mobilization of a crane. We could mobilize a crane at an additional cost.
- 3) An additional 14 Contract days are requested for implemtation of this proposal.

PROJECT: 15176 WCD#

ITEM SHEET COSTS

Date: 8/31/2016 11:52:21 A

AS SHOWN

ITEM:
DESCRIPTION:

10

STEEL SHEET PILE WINGWALL

UM: BID QTY: SF

STEEL SHEET FILE WINGWALL

TO QTY:

2550.00 2550.00

COST CODE:

PRODUCTION: HRS/DAY:

Days 10 TOTAL MHS: MHS/UNIT:

300.00 0.1176

UNITS/MH:

8.5000

Item Production

<u>ITEM#</u> 10 DESCRIPTION
STEEL SHEET PILE WINGWALL

U/M SF QTY 2550.00 <u>UNITS/DAY</u> 425,00

DAYS REQD

6.00

Cost Detail for Item 10

C CODE	<u>DESCRIPTION</u>	QUANTITY U/M	FACTORS	RATE	<u>COSTS</u>		
DRIVE 25 PRS OF EXISTING PZ-22 x 30'							
L 02	FOREMAN	1.000	6.000	500.392	3002.35		
L 03	CRANE OPERATOR	1.000	6.000	411.248	2467.49		
L 06	PILEDRIVERS	3.000	6.000	301.912	5434.42		
E 25	110T TEREX	1.000	6.000	1000.000	6000.00		
E 06A	CAT 322 EXCAVATOR	1.000	6.000	670,000	4020.00		
E 14	BIG TOOL '	1.000	6.000	100.000	600.00		
E 14A	SMALL TOOL	1.000	6.000	37.800	226.80		
E 15	PICKUP	1.000	6.000	140.000	840.00		
R 09	MKT V-5(DAY)	1.000	6.000	620.000	3720.00		
R 02	60' MANLIFT	1.000	6.000	302.500	1815.00		
ST CHARLES PARISH SHALL FURNISH SHEETS							
M 17	PZ-22 SHEET PILE	0.000 LB	1.000	0.709	0.00		
M 18	SHEET PILE COATINGS	0.000 SF	1.000	3.270	0.00		
M 19	SHEET PILE CORNERS	0.000 LF	1.000	70.850	0.00		

Item Unit Cost: 11.03

Item Total Cost:

28,126.06

Total: Unit: <u>Labor</u> 10,904.26 4.28 Equipment 11,686.80 4,58 Rental Eq 5,535.00 2.17

<u>Material</u> 0.00 0.00

Subcontract 0.00 0.00

Other 0.00 0.00

Bid Data for Item: 10

Bid Qty. Takeoff Qty. Quantity 2,550.00 2,550.00 Bid Unit 12.90 12.90 Bid Amt. 32,895.00 32,895.00 Total Cost 28,126.06 28,126.06 Prof & Ovhd 4,768.94 4,768.94 Windfall 0.00

BID SHEET

Page:1

PROJECT: 15176 WCD #

Description

WILLOWRIDGE PUMP STATION

ADDITIONAL SHEET PILE & RIP RAP

Bld Date

08/26/2016

Revised

Location ST. CHARLES PARISH
Contract # BURK KLEINPETER, INC

Bld Comments:

Qualifications:

1) The sheet pile materials shall be supplied by St Charles Parish and shall be in a condition to allow for installation

2) This proposal does not include mobilization of a crane. We could mobilize a crane at an additional cost.

3) An additional 14 Contract days are requested for implementation of this proposal. }

BID SHEET

Page:2

PROJECT: 15176 WCD#

Description

WILLOWRIDGE PUMP STATION ADDITIONAL SHEET PILE & RIP RAP

BID SUMMARY

	MARKUP %	MARKUP AMT	TOTAL	
LABOR	0.00%	0.00	10,904.26	33.17%
EQUIPMENT	0.00%	0.00	11,686.80	35.55%
RENTAL EQ	0.00%	0.00	5,535.00	16.84%
MATERIAL	0.00%	0.00	0.00	0.00%
SUBCONTRACT	0.00%	0.00	0.00	0.00%
OTHER	0.00%	0.00	0.00	0.00%
TOTAL DIRECT COSTS	S:		28,126.06	85.55%
PROJECT OVERHEAD TABLE	0.00%	0.00	0.00	0.00%
PROJECT OVERHEAD	0.00%		0.00	0.00%
TOTAL JOB COSTS	S:		28,126.06	85.55%
TOTAL DIRECT COSTS MARKUP AMT			0.00	0.00%
CORPORATE OVERHEAD	5.00%		1,406.30	4.28%
NET PROFIT .	10.00%		2,988.74	9.09%
SUBTOTAL	L:		32,521.10	98.92%
TAXES - ADD ON - DEDUCT	0.00%		0.00	0.00%
BOND COSTS FROM TABLE (Y/N)	Yes		355.06	1.08%
TOTAL MARKUP SPREAD TO ITEMS	* * * *		4,750.11	14.45%
		BALANCED BID:	32,876.16	100.00%
		ACTUAL BID:	32,895.00	100.0075
		JNBALANCED AMT:	18.84	
	`)(4D/12) (1OLO /11)) .	10.01	
		ACTUAL MARGIN:	4,768,94	
•	PF	ROPOSED MARGIN:	4,750,11	
	•••			
	UNIT MARK-UP ON TOTAL D	DIRECT COST :	0.1689	
	UNIT MARK-UP ON TOTAL J	OB COSTS :	0.1689	
	MARK-UP ON SALES	:	0.1445	•

8/31/2016 11:53:03 AM

BID SHEET

Page:3

PROJECT: 15176 WCD#

 Item
 Description
 U/M
 Bid Qty
 T/O Qty
 Total Cost
 Unit Cost
 Margin
 Bid Unit
 Total Bid
 +/

 10
 STEEL SHEET PILE W
 SF
 2550.00
 2550.00
 28126.06
 11.03
 12.89
 12.90
 32895.00
 4768.94

TOTALS: 28126.06 32895.00 4768.94


8/31/2016 11:53:03 AM

BID SHEET

Page:4

PROJECT: 15176 WCD#

		Labor Unit	Equip Unit	Rental Unit	Material Unit	Subcont Unit	Other Unit
Item	Description	Total	Total	Total	Total	Total	Total
		4.28	4.58	2.17	0.00	0.00	0.00
10	STEEL SHEET PILE WINGW	10904.26	11686.80	5535,00	0.00	0.00	0.00
	TOTALS:	10904.26	11686.80	5535.00	0.00	0.00	0.00



•