CHANGE ORDER				
			No.	1
DATE OF ISSUANCE December 5, 2003		EFFECTIVE DATE	December 5, 200	<u>13</u>
OWNER St. Charles Parish (SCP) Council CONTRACTOR Civil Construction Contract Contract: Bayou Gauche Walking Track	ctors, Inc.			
Project. Bayou Gauche Walking Track OWNER's Contract No. P0: ENGINEER J. Michael Dixon, Consul	20802 ting Engineer	ENGINEER's Contract	No.	N/A
You are directed to make the following changes Description: See Attachment 1 - Desc	ription of Changes		_	
Reason for Change To provide additional exc Order	avation, limestone, fill	and grading to bridge ov	er wet area	
Attachments: (List documents supporting change	e) Attachment	1 - Description of Chang	ges	
CHANGE IN CONTRACT PRICE		CHANG	GE IN CONTRACT TIME	₹S
Original Contract Price: _\$51,839.00		Original Contract Times Substantial Completion Ready for final payment		
Net increase from previous Change Orders No. <u>Q</u> to No. <u>Q</u> :		Net change from previous Ch No. <u>0</u> : Substantial Completion 3	nange Orders No g to	
<b>\$0.00</b>		Ready for final payment.		
Contract Price pnor to this Change Order: \$51,839.00		Contract Times prior to this C Substantial Complotion: Ready for final payment;	hange Order; September 24, 2003	
Not increase of this Change Order:		Net increase from this Chang	e Order:	
\$3,538.00		Substantial Completion: Ready for final payment;	•	
Contract price with all approved Change Orders \$55,377 00		Contract Times with all appro Substantial Completion: C Ready for final payment: L	October 17, 2003	
RECOMMENDED:  By: Laboratore  ENGINEER (Authorized Signature)  Date: 12/5/3*2	APPROVED: By: / blust / C OWNER (Authorized Signate: - / 18/ 1	- <i>L</i> A	TED:  Whe Such  ACTOR (Authorized Sign  12-9-03	S) gneture)

Prepared by the Engineers Joint Contract Documents Committee and ondersed by The Associated General Contractors of America and the Construction Specifications inclinity

EJCDC 1910-8-6 (1996 Edition)

## **Bayou Gauche Walking Track Public Works Project P020820**

## Description of Changes for Change Order No. 1

On or about September 4, 2003, the Contractor noticed that there was a large area near the north west corner of the project where standing water was occurring. A subsequent inspection indicated that one of the property owners to the north had an open, flowing well on his property. Within a day or two, the Parish and the Contractor had the well closed off and the flow stopped. The Contractor was then instructed to wait and see if the area would dry sufficiently to complete the project without the institution of work beyond the scope of the original Contract Documents.

After two weeks, the area still had not dried sufficiently to complete the work in accordance with the original Contract Documents. Accordingly, the Contractor was instructed to provide a price to excavate an area approximately 15 feet wide by 85 feet long and 2 feet deep. This area would be layered with a geotextile fabric and backfilled with compacted pump sand. The Contractor subsequently provided a quote of \$3,538.00 to perform this work This price was verbally accepted on September 20, 2003 and the Contractor was instructed to proceed with the extra work. The total extra time involved with this Change is 23 calendar days.