



St. Charles Parish - School Zone Traffic Study - Planning Stage Cost Estimate				Date: 10/29/2025	
ITEM NO.	ITEM DESCRIPTION	Unit	Unit Price	Qty.	Total Cost
S1-1	SCHOOL SIGN (30"x30")	EACH	\$ 105.00	61	\$ 6,405.00
S4-3P	SCHOOL SIGN (24"x9")	EACH	\$ 50.00	93	\$ 4,650.00
S4-1P	TIME OF DAY SIGN (24"x12")	EACH	\$ 55.00	60	\$ 3,300.00
R2-1	SPEED LIMIT (SCHOOL USE) SIGN (24"x30")	EACH	\$ 160.00	44	\$ 7,040.00
R2-6aP	FINES DOUBLE SIGN (24"x18")	EACH	\$ 60.00	66	\$ 3,960.00
S5-2	END SCHOOL ZONE SIGN (24"x30")	EACH	\$ 160.00	25	\$ 4,000.00
W16-9P	AHEAD SIGN (24"x12")	EACH	\$ 55.00	14	\$ 770.00
S4-4P	WHEN FLASHING SIGN (24"x12")	EACH	\$ 55.00	2	\$ 110.00
HFZ (large)	HANDS FREE ZONE SIGN BIG	EACH	\$ 120.00	22	\$ 2,640.00
HFZ (small)	HANDS FREE ZONE SIGN SMALL (24"x12")	EACH	\$ 55.00	42	\$ 2,310.00
NS-736-00013	RADAR SPEED ALERT SIGN POST MOUNTED (SOLAR)	EACH	\$ 3,200.00	20	\$ 64,000.00
NS-ITS-10030	SOLAR POWER SYSTEM, FURNISH & INSTALL	EACH	\$ 1,000.00	20	\$ 20,000.00
732-01-01080	PLASTIC PAVEMENT STRIPING (24" WIDTH)(THERMOPLASTIC 125 MIL)	LIN. FT.	\$ 15.00	6,770	\$ 101,550.00
732-04-19020	PLASTIC PAVEMENT LEGENDS AND SYMBOLS (SCHOOL)	EACH	\$ 650.00	53	\$ 34,450.00
POSTS	U-CHANNEL SIGN POSTS	EACH	\$ 150.00	173	\$ 25,950.00
713(01)	TEMPORARY SIGNS AND BARRICADES	LUMP	\$ 10,000.00	1	\$ 10,000.00
727(01)	MOBILZATION (5% of above total)	LUMP	\$ 14,056.75	1	\$ 14,056.75
				Subtotal Cost =	\$ 305,191.75
				Contingency (20%) =	\$ 61,038.35
				<b>ESTIMATED CONSTRUCTION COST =</b>	<b>\$ 366,230.10</b>
				<b>ESTIMATED COST PER TRAFFIC ZONE (15 TOTAL)=</b>	<b>\$ 24,415.34</b>